

DOCUMENTO ORIGINAL EN MAL ESTADO

Appendix D

Preliminary Brief Prepared by a Ministry of Health

The following working documents show how a Ministry of Health was able to standardise information and give efficient instructions of its wishes to counterparts in the Ministry of Construction. The documents exhibit some omissions, for example, electrical installations. However, these were discussed later.

DATE

GOVERNMENT OF ZIMBABWE, SECOND FAMILY HEALTH PROJECT, MINISTRY OF HEALTH DESIGN BRIEF

LIST OF DIFFERENT FUNCTIONAL REQUIREMENTS FOR KEY MATERIALS FINISHES INSTALLATIONS & FITTINGS

FLOOR FINISHES	
FL 01	Normal floors in habitable rooms
FL 02	Floors in wet areas
FL 03	Floors in clean areas
FL 04	Floors in heavy trafficked areas
FL 05	Floors in stores and other non habitable rooms
FL 06	Floors in covered ways and semi open waiting areas
WALL FINISHES	
WF 01	Normal walls in habitable rooms
WF 02	Walls in wet areas
WF 03	Walls in clean areas
WF 04	Walls in heavy trafficked areas
WF 05	Walls in stores and other non habitable rooms
DOORS	
DO 01	700 mm door, internal
DO 02	800 mm door, internal
DO 03	900 mm door, internal
DO 04	900 mm door, external, normal
DO 05	900 mm door, external, heavy duty
DO 06	1400 mm double door, internal
DO 07	1400 mm double door, external, normal
DO 08	1600 mm double door, external
DO 09	Special doors
WINDOW SEATINGS (It is impossible to give window sizes at this stage)	
WS 01	Window sill at 900 mm
WS 02	Window sill at 1,100 mm
WS 03	Window sill at 1,500 mm
HAND WASH BASINS AND SINKS	
HS 01	HNB, normal → ALL SHOULD BE HEAVY DUTY
HS 02	HNB, heavy duty
HS 03	Trough, 1,200 mm long
HS 04	Sink, Belfast (A LARGER VARIETY OF KITCHEN SINKS, GAB
HS 05	SINK, Kitchen (SINKS WILL BE REQUIRED
URINALS	
UR 01	Urinal 1,200 mm long, normal
UR 02	Urinal 1,200 mm long, heavy duty
BATHS AND SHOWERS	
BS 01	Bath, built-in, normal
BS 02	Bath assisted, free standing
BS 03	Shower, normal
BS 04	Shower, heavy duty
W.C.'S AND OTHER SANITARY FITTINGS WITH LARGE BODIES	
WC 01	W.C. normal
WC 02	W.C. heavy duty
WC 03	W.C. children
WC 04	W.C. floor model
WC 05	Stop hopper (what other fittings)
WC 06	Laboratory waste outlet
FLOOR OUTLET	
FO 01	Floor outlet, side dispensing
FO 02	Floor outlet, vertical trap
LIGHTING	
LI 01	General lighting, fluorescent
LI 02	General lighting, incandescent
LI 03	Special lighting, examination lights, op. th. light
LI 04	Emergency lighting, standby
WATER OUTLETS	
WO 01	440 V socket outlet
WO 02	380 V socket outlet

2 SHOULD BE SURGICAL

IN ARE HEAVY DUTY
normal different size

both heavy duty only ones
are different

IN ARE HEAVY DUTY, LAST ONE
are different?

more detailed list schedule
is required

DATE 05 JUNE 91 M4 1

GOVERNMENT OF ZIMBABWE. SECOND FAMILY HEALTH PROJECT. MINISTRY OF HEALTH DESIGN BRIEF

MINISTRY OF HEALTH COMMENTS REGARDING SPECIFICATION OF KEY MATERIALS FINISHES INSTALLATIONS & FITTINGS

Subject to information

FLOOR FINISHES

- FL 01 Normal floors in habitable rooms. Must not be thermo-plastic/Vinyl Tiles/home slip finish - finished screed. [paint/epoxy]
- FL 02 Floors in wet areas. Not vinyl tile, preferably terrazzo/mar or screed with plastic floor. Should finish floor in both terrazzo, or screed with plastic finish. Not vinyl tiles, home slip finish. Tiles or screed/home slip finish. → check paving, etc. for any concrete or wall.
- FL 03 Floors in clean areas. Screed.
- FL 04 Floors in heavy trafficked areas. Tiles or screed/home slip finish.
- FL 05 Floors in stores etc.
- FL 06 Floors in covered ways, etc. Tiles or screed/home slip finish.

WALL FINISHES

- WF 01 Normal walls in habitable rooms. Plaster with plastic paint. (No form plaster in wet areas and corridors - at least 10/15m)
- WF 02 Walls in wet areas. Plaster with enamel paint: could be with glass fibre mesh.
- WF 03 Walls in clean areas. Plaster with egg shell enamel. Handwashed crash vault.
- WF 04 Walls in heavy trafficked areas. Plaster with enamel paint/or left unplastered or unplastered.
- WF 05 Walls in stores, etc. mechanical

DOORS

- DO 01 700mm door internal. Should be as solid as possible with hinges and immovable to water.
- DO 02 800mm door internal. As above.
- DO 03 900mm door internal. As above. Consider protection against theft etc.
- DO 04 900mm door external, normal. As above: in steel frame in Zimbabwe. Glazing if required with extra mesh glass.
- DO 05 900mm door external, heavy duty. Steel.
- DO 06 1400mm door internal [double]. As above.
- DO 07 1400mm double door external. As above.
- DO 08 1800mm double door external. As above.

WINDOWS

- WF 01 Window frames. Rolled steel, heavy duty.
- WF 02 Glazing. Heavy duty. Perm and aesthetically are important.
- WF 03 Security bars. Steel.
- WF 04 Ventilation panels. Steel.

HANDWASH BASINS AND SINKS

- HS 01 HWB normal. Must not be domestic quality. Use support required. Good quality taps.
- HS 02 HWB heavy duty. In stainless steel frame in Zimbabwe? Strong legs support important.

A P P E N D I C E S

DATE 05 JUNE 91 AMH .2

GOVERNMENT OF ZIMBABWE SECOND FAMILY HEALTH PROJECT MINISTRY OF HEALTH DESIGN BRIEF

MINISTRY OF HEALTH COMMENTS REGARDING SPECIFICATION OF KEY MATERIALS FINISHES INSTALLATIONS & FITTINGS

- HS 03 Trough, 1,200 mm long. Stainless steel pit-chime, or asbestos cement?
- HS 04 SINK, Belfast. Porcelain/stove ware. Wood protection on top rim
- HS 05 SINK kitchen. Different types. Lowest support must be substantial.
- URINALS
 - UR 01 Urinal, 1,200 mm long normal. Stainless steel
 - UR 02 Urinal, 1,200 mm long, heavy duty. Built in.
- BATHS AND SHOWERS
 - BS 01 Bath, built in, normal. Cart non?
 - BS 02 Bath, assisted. Free standing. Cart non.
 - BS 03 Shower, normal.
 - BS 04 Shower, heavy duty.
- WC'S, SLOP HOPPERS ETC.
 - WC 01 WC normal
 - WC 02 WC heavy duty. Heavy wotren feet preferred to plastic - high level custom. Built in feet slugs. could be stainless steel. high level cart non custom.
 - WC 03 WC children. As above.
 - WC 04 WC floor model. Stainless steel?
 - WC 05 Slop hopper. As above, stainless steel?
 - WC 06 Laboratory waste outlet. What is this?
- FLOOR OUTLET.
 - FO 01 Floor outlet, side air passage. Sliding cap essential.
 - FO 02 Floor outlet, vertical trap. Ditch.
- LIGHTING
 - L1 01 General lighting, fluorescent.
 - L1 02 General lighting, tungsten.
 - L1 03 Special light, examination, OP. Question whether built in or mobile? Standing ballasts?
 - L1 04 Emergency lighting. Emergency lighting must be mounted to minimum NOT in work area.
- POWER OUTLETS
 - PO 01 240 V. socket outlet.
 - PO 02 380 V socket outlet.

DATE 05, JUNE 91 AMH.
SHEET ST 001

GOVERNMENT OF ZIMBABWE, SECOND FAMILY HEALTH PROJECT, MINISTRY OF HEALTH DESIGN BRIEF

PROJECT PERMITMENT
REVISED STOCK-TYPE PLANS **OUTPATIENTS DEPARTMENT**

DEPARTMENT	ROOM NUMBERS	ZONE	NUMBER OF ROOMS	M ² PER ROOM	M-TOTAL	RESURFACING	FLOOR FINISH	WALL FINISH	DOORS	WINDOW SEATING	MASHING/GRANS	N.C./S/S/SLIP HOPPER	URINALS A OR B	BATH SHOWERS	FLOOR SUTTER	CEILING	POWER SUTTER	POWER SUTTER	WATER SUPPLY	WASTE WATER SYSTEM	
OP	01	Admissions	1 no	9	9	01	01	02	01	01	01	-	-	-	-	-	01/10	01/10	-	-	
OP	02	Records	1 no	34	34	04	04	02	03	03	-	-	-	-	-	-	01/10	01/10	-	-	
OP	03	MA Consulting	2 no	17	34	01	01	03	01	10	10	-	-	-	-	-	01/20	01/20	-	-	
OP	04	Doctor Consulting	2 no	17	34	01	01	03	01	10	10	-	-	-	-	-	01/20	01/20	-	-	
OP	05	Staff lockers	1 no	17	17	04	04	02	03	03	03	10	-	03	-	-	10	10	-	-	
OP	06	Dentist	1 no	17	17	01	01	03	01	01	01	-	-	-	-	-	01/20	01/20	-	-	
OP	07	Pressings/breadst	1 no.	17	17	02	02	03	01	01	01	-	-	-	-	-	01/20	01/20	-	-	
OP	08	Injections	1 no.	17	17	02	02	03	01	01	01	-	-	-	-	-	01/20	01/20	-	-	
OP	09	Cleaner/Sluice	1 no	12	12	02	02	03	02	02	02	05	-	-	-	-	01/04	01/04	-	-	
OP	10	Laboratory	1 no.	58	58	01	01	03	02	01	01	-	-	-	-	-	01/04	01/04	-	-	
OP	11	Toilets, female	1 no	17	17	02	02	02/01	03	02	02	02/20	-	-	-	-	10	10	-	-	
OP	12	Toilets, male	1 no.	17	17	02	02	02/01	03	02	02	02/20	-	-	-	-	10	10	-	-	
OP	13	Waiting areas	1 no	-	[30]	02	02	02/01	03	02	02	02/20	-	-	-	-	10	10	-	-	
OP	14	Corridor, 2m wide	-	-	-	06	06	-	-	-	-	-	-	-	-	-	-	-	-	-	
TOTALS																					
WHOLE DEPARTMENT CIRCULATION			%	NET	283																
WHOLE DEPARTMENT				50	140																
EXTERNAL WAITING				423	90																

Some containers at this site of the different types

* See detail schedule
Possible Z areas. Fafal 90
Mainly open.

APPROVALS

DATE
05 JUNE 01. AMH
RIFET
ST. 005

GOVERNMENT OF ZIMBABWE, SECOND FAMILY HEALTH PROJECT, MINISTRY OF HEALTH DESIGN BRIEF
DEPARTMENT

REVISIED STOCK-TYPE PLANS
DIAGNOSTIC X-RAY

ROOM NUMBER	ROOM DESCRIPTION	NUMBER OF ROOMS	M - RSR ROOM	M - STAFF	WALL PROTECTION	DOOR	SHADOW CASTING	SCREENS	EXPOSURE	CONTROL	POWER POINTS	TELEVISION	APPROVALS
XR 01	Diagnostic X-ray rm.	1	28	28	1*	3*	3	1/1m	1	1/1*	1/1m	1	** fee special standard
XR 02	Dark room	1	5	5	2	1	1	1/1m	1	1/1*	1/1m	1	
XR 03	Viewing room	1	8	8	1	2	3	1/1m	1	1/1*	1/1m	1	
XR 04	Film store	1	5	5	5	2	3	1/1m	1	1/1*	1/1m	1	
XR 05	Reception office	1	8	8	1	3	2	1/1m	1	1/1*	1/1m	1	
XR 06	Barium Toilet/prep.	1	5	5	2	2	3	1/1m	1	1/1*	1/1m	1	
XR 07	Waiting/corrid. 2.4m	-	-	[24]	6	6	6	-	-	-	-	-	
XR 08	Change cubicle	2	2	4	1	1	1	-	-	-	-	-	
TOTALS	WHOLE DEPARTMENT CIRCULATION WHOLE DEPARTMENT EXTERNAL WAITING	%	NET	GROSS	# With protection	# With protection	# With protection						
			61	84	85	-							

APPENDICES

DATE 05 JUNE 91, MH

PROJECT GOVERNMENT OF ZIMBABWE, SECOND FAMILY HEALTH PROJECT, MINISTRY OF HEALTH DESIGN BRIEF

SHEET ST 006

OPERATING THEATRE DEPARTMENT

REVISED STOCK-TYPE PLANS

ROOM NUMBER	DESCRIPTION	NUMBER OF ROOMS	M - PER ROOM	M - TOTAL	NO. OF STAFF	NO. OF PATIENTS	NO. OF VISITORS	NO. OF ATTENDANTS	NO. OF OTHERS	NO. OF TOTALS	NO. OF STAFF	NO. OF PATIENTS	NO. OF VISITORS	NO. OF ATTENDANTS	NO. OF OTHERS	NO. OF TOTALS	NO. OF STAFF	NO. OF PATIENTS	NO. OF VISITORS	NO. OF ATTENDANTS	NO. OF OTHERS	NO. OF TOTALS	
OP 01	Operating theatre	1	36	36	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
OP 02	Scrub-up	1	9	9	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
OP 03	Staff change [m]	1	12	12	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
OP 04	Staff change [f]	1	12	12	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
OP 05	Equipment store	1	12	12	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
OP 06	Staff room	1	12	12	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
OP 07	Sister's office	1	12	12	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
OP 08	Recovery	1	36	36	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
OP 09	Sluice/disposal	1	6	6	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
OP 10	Patients waiting	1	18	18	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
TOTALS	WHOLE DEPARTMENT		NET	167																			
	CIRCULATION		40	6.7																			
	WHOLE DEPARTMENT		GROSS	234																			
	EXTERNAL WAITING																						

APPROVALS

APPENDICES

DATE 05 JUNE 1991 MH
PROJECT DIRECT

GOVERNMENT OF ZIMBABWE, SECOND FAMILY HEALTH PROJECT, MINISTRY OF HEALTH DESIGN BRIEF

REVISD STOCK-TYPE PLANS
PERMPMENT LAVNDRY
ST 012

ROOM NUMBER	Z.M.	DESCRIPTION	NUMBER OF ROOMS	M - PER ROOM	M - TOTAL	WALL FINISH	FLOOR FINISH	CEILING FINISH	WINDOW SEATING	* WASHING STATIONS	W.C.S	WASHING A 2 B	BATH SHOWERS	FLOOR OUTLET	VENTILATION	POWER OUTLETS	TELEPHONE	APPROVALS
LA 01		Dirty linen recept	1	22	22	2	2		2	2								
LA 02		Washing	1	28	28	2	2		2	2								
LA 03		Mending/ironing	1	22	22	2	2		2	2								
LA 04		Clean linen store	1	22	22	5	5		3	2								
TOTALS		WHOLE DEPARTMENT CIRCULATION IN HOLE DEPARTMENT EXTERNAL WAITING		NET	80													
			%	GROSS														

APPROVALS

* Special schedule

Special schedule

